



PLOTTED: 10/27/2013 9:51 AM
 SAVD: 9/10/2013 11:01 AM Trade L. Zerr
 G:\Projects\159\159-P5-001 Well Installations 10-2012\Civil-Dwg\As-Recorded\Well Site Plan.dwg



SITE PLAN
 URNRD AUGMENTATION WELL #7

- NOTES:
- ALL 10" WATER MAIN THROUGH METER PIT SHALL BE CLASS 350 DUCTILE.
 - CONTRACTOR TO COORDINATE W/ SWPPD FOR POWER POLE LOCATION/REQUIRED DISCONNECT AND ALL UNDERGROUND FROM POWER POLE TO PANEL BOXES. POWER POLE TO BE MIN. 50' AWAY BUT NO GREATER THAN 75'.
 - CONDUIT RUNS NOT SHOWN.
 - CONTRACTOR VERIFY CONNECTION POINT BURY DEPTH PRIOR TO INSTALLING PITLESS UNIT.
 - PIPING SHALL BE LAID TO ALLOW FOR AIR RELEASE TO EXISTING TRANSMISSION MAIN OR AIR RELEASE IN METER PIT.



TEST PUMP DATA - WELL #7		
	START WATER LEVEL	END WATER LEVEL
AUG. WELL #7	70.856	138.243
AUG. WELL #8	87.946	88.629
AUG. WELL #9	89.952	90.148

SPECIFIC
 CAPACITY
 20.8

FINAL HP	125
PUMP BOWLS	9TLC
TRIM	?
STAGE	2

URNRD AUGMENTATION WELL #7
 CONSTRUCTION
 (SWL 78' 11-21-2012)

REVISIONS	BY

Miller & Associates
 Consulting Engineers, P.C.
 Kearney, NE (308) 234-6456
 McCook, NE (308) 345-3710

URNRD - AUGMENTATION - WATER SUPPLY WELLS & PIPING
 URNRD AUGMENTATION WELL #7
 DUNDY COUNTY, NEBRASKA

This document, and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Miller & Associates and is not to be used in whole or in part, for any other project without the written authorization of © 2009 Miller & Associates.

"AS RECORDED"

FROM INFORMATION PROVIDED BY THE CONTRACTOR.
 DATE: 07-2013 BY: TLZ
 THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY CHRIS A. MILLER (E-8775), ON 12/10/2012.
 THIS MEDIA SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT.

FINAL HP	125
PUMP BOWLS	9TLC
TRIM	?
STAGE	2

VERIFY SCALES

BAR IS ONE INCH ON ORIGINAL DRAWING
 0 1"
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

SCALE: AS SHOWN

PROJECT NO. 159-P5-001

DATE: DECEMBER, 2012

FIELD BOOK	M&A DWG NO. 25308
DRAWN BY: BSF	APRVD BY:

SHEET 12