



PLOTTED: 9/10/2013 2:14 PM Title: L. Zerr  
 Saved: 9/10/2013 2:14 PM Title: L. Zerr  
 C:\Projects\159\159-P5-001\Well Installations 10-2012\Civil-Dwg\As-Recorded\Well Site Plan.dwg





SITE PLAN  
 URNRD AUGMENTATION WELL #4

- NOTES:
- ALL 10" WATER MAIN THROUGH METER PIT SHALL BE CLASS 350 DUCTILE.
  - CONTRACTOR TO COORDINATE W/ SWPPD FOR POWER POLE LOCATION/REQUIRED DISCONNECT AND ALL UNDERGROUND FROM POWER POLE TO PANEL BOXES. POWER POLE TO BE MIN. 50' AWAY BUT NO GREATER THAN 75'.
  - CONDUIT RUNS NOT SHOWN.
  - CONTRACTOR VERIFY CONNECTION POINT BURY DEPTH PRIOR TO INSTALLING PITLESS UNIT.
  - PIPING SHALL BE LAID TO ALLOW FOR AIR RELEASE TO EXISTING TRANSMISSION MAIN OR AIR RELEASE IN METER PIT.



TEST PUMP DATA - WELL #4		
	START WATER LEVEL	END WATER LEVEL
AUG. WELL #4	108.578	151.658
OLD #4	92.726	95.317
AUG. WELL #3	93.806	94.324


SPECIFIC  
 CAPACITY  
 32.5



URNRD AUGMENTATION WELL #4  
 CONSTRUCTION

FINAL HP	125
PUMP BOWLS	11CLC
TRM	6.875
STAGE	2

REVISIONS	BY



**Miller & Associates**  
 Consulting Engineers, P.C.  
 Kearney, NE (308) 234-6456  
 McCook, NE (308) 345-3710

URNRD - AUGMENTATION - WATER SUPPLY WELLS & PIPING  
**URNRD AUGMENTATION WELL #4**  
 DUNDY COUNTY, NEBRASKA

"AS RECORDED"  
 FROM INFORMATION PROVIDED BY THE CONTRACTOR.  
 DATE: 07-2013 BY: TLZ  
 THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY CHRIS A. MILLER (E-8775), ON 12/10/2012.  
 THIS MEDIA SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT.

**VERIFY SCALES**  
 BAR IS ONE INCH ON ORIGINAL DRAWING  
 0 1"  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

SCALE: AS SHOWN  
 PROJECT NO. 159-P5-001  
 DATE: DECEMBER, 2012  
 FIELD BOOK M&A DWG NO. 25313  
 DRAWN BY: BSF APRVD BY:  
 SHEET 7