


PLOTTED: 9/10/2013 10:55 AM
 SAVED: 9/30/2013 2:14 PM Title: L. Zerr
 C:\Projects\159\159-P5-001\Well Installations 10-2012\Civil-Dwg\As-Recorded\Well Site Plan.dwg



SITE PLAN
 URNRD AUGMENTATION WELL #3

- NOTES:
- ALL 10" WATER MAIN THROUGH METER PIT SHALL BE CLASS 350 DUCTILE.
 - CONTRACTOR TO COORDINATE W/ SWPPD FOR POWER POLE LOCATION/REQUIRED DISCONNECT AND ALL UNDERGROUND FROM POWER POLE TO PANEL BOXES. POWER POLE TO BE MIN. 50' AWAY BUT NO GREATER THAN 75'.
 - CONDUIT RUNS NOT SHOWN.
 - CONTRACTOR VERIFY CONNECTION POINT BURY DEPTH PRIOR TO INSTALLING PITLESS UNIT.
 - PIPING SHALL BE LAID TO ALLOW FOR AIR RELEASE TO EXISTING TRANSMISSION MAIN OR AIR RELEASE IN METER PIT.

TEST PUMP DATA - WELL #3		
	START WATER LEVEL	END WATER LEVEL
AUG. WELL #3	93.681	136.228
OLD #3	95.819	99.276
AUG. WELL #4	108.894	109.644
AUG. WELL #5	71.831	73.266

SPECIFIC
 CAPACITY
 32.9

FINAL HP	125
PUMP BOWLS	11CLC
TRM	6.875
STAGE	2

URNRD AUGMENTATION WELL #3
 CONSTRUCTION

REVISIONS
 BY

Miller & Associates
 Consulting Engineers, P.C.
 Kearney, NE (308) 234-6456
 McCook, NE (308) 345-3710

URNRD - AUGMENTATION - WATER SUPPLY WELLS & PIPING
 URNRD AUGMENTATION WELL #3
 DUNDY COUNTY, NEBRASKA

"AS RECORDED"
 FROM INFORMATION PROVIDED
 BY THE CONTRACTOR.
 DATE: 07-2013 BY: TLZ
 THIS DOCUMENT WAS ORIGINALLY
 ISSUED AND SEALED BY
 CHRIS A. MILLER
 (E-8775), ON
 12/10/2012.
 THIS MEDIA SHOULD NOT
 BE CONSIDERED A
 CERTIFIED DOCUMENT.

VERIFY SCALES
 BAR IS ONE INCH ON
 ORIGINAL DRAWING
 0 1"
 IF NOT ONE INCH ON THIS
 SHEET, ADJUST SCALES
 ACCORDINGLY.

SCALE: AS SHOWN
 PROJECT NO. 159-P5-001
 DATE: DECEMBER, 2012
 FIELD BOOK M&A DWG NO. 25314
 DRAWN BY: BSF APRVD BY:
 SHEET

6